DATE SUBMITTED	7/25/24	COUNCIL PUBLIC H
SUBMITTED BY	Public Services	RESOLUT
	8/7/24	ORDINAN
DATE ACTION REQUIRED	0/1/24	ORDINAN
		CITY CLE

Agenda Item No	
COUNCIL ACTION	(X)
PUBLIC HEARING REQUIRED	()
RESOLUTION	()
ORDINANCE 1ST READING	()
ORDINANCE 2 ND READING	()
CITY OF EDVIC INITIAL C	()

IMPERIAL CITY COUNCIL AGENDA ITEM

UBJECT: DISCUSSION/ACTION:					
 Approve purchas plant 					
DEPARTMENT INVOLVED: Public Services					
BACKGROUND/SUMMARY: A flow meter is an instrument used to measure the flow rate 22-inch diameter magnetic flow meter to measure influent ra	e of liquids, gases, or vapors through a pipe or conduit. The city utilizes a aw water flows at the water plant.				
as the mag meter. The purchase and replacement of the mag	cement. City staff is using a backup insertion meter that is not as accurate agnetic flow meter will allow the water treatment plant staff to avoid r fail, the City will not be able to determine how much raw water is being				
The replacement meter being requested will be purchased a utilized this agency thus they have the experience and known	and installed through Control Systems Engineering. City has previously wledge of our system.				
Total cost is \$22,856.43. Cost includes all equipment, labor	and materials to complete replacement.				
FISCAL IMPACT: NOT TO EXCEED \$22,856.43 (52-510-5442)	FINANCE INITIALS VMS				
STAFF RECOMMENDATION: approve request	DEPT. INITIALS DO				
MANAGER'S RECOMMENDATION:	CITY MANAGER'S INITIALS				
MOTION:					
SECONDED: AYES: NAYES: ABSENT:	APPROVED () REJECTED () DISAPPROVED () DEFERRED () REFERRED TO:				

Control Systems Engineering, Inc. PO Box 25180 Yuma, AZ 85367

WRITTEN ESTIMATE

DATE:

7/10/2024

EST NUMBER: FM-071024

CUSTOMER NAME / ADDRESS

City of Imperial 420 South Imperial Ave Imperial, CA 92251

PROJECT ADDRESS:

City of Imperial		
Raw Water Flowmeter		

ITEM	DESCRIPTION	QTY	VALUE	EXTENDED
89002	Raw Water Flowmeter Replacement - Refer to Patten Systems Quote #Q2407-007 (with tax, delivery and contractor markup).	1	19,776.43	19,776.43
89002	On-site labor and miscellaneous materials.	1	3,080.00	3,080.00

Phone #

Fax # (951)551-6347

ESTIMATED COSTS:

\$22,856.43

PATTEN SYSTEMS, INC.

15598 Producer Lane Huntington Beach, CA 92649 Tel: (714)-799-5656

July 3, 2024

Control Systems Engineering

Attn: Eric Blom

2299 Winterhaven Drive Suite 508

Winterhaven, CA 92283

Ph: 951-551-6347

eric@controlsystemseng.com

Quote #Q2407-007

As a Representative for Sparling Instruments, we are pleased to offer our quotation for the following:

Reference Information

Flow Range: 0-7,000 GPM Flow Media: Raw Water

Cable Length on meter record is 50 ft. (7.25/ft. over 50 ft.). Please confirm

cable length needed before placing your order

Item 1

Raf: Replacement for S/N M202233716

Qty 1

Sparling Magnetic Flow Meter, Tigermag Series

FM656 = Flanged Style Meter

20 = 20" Size

5 = Polyurethane Liner

1 = 316SS Electrodes

A = Flanged 150# ANSI B16.5
3= Remote Mount NEMA 4X/7 Enclosure with accidental submergence proof

sensor and 50 ft. of cable (7.25/ft. over 50 ft.)

1= 24 VDC Power

HART = HART Protocol Included

AC615-20-1 = 20" 304SS Grounding Rings

Part No. FM656-205-1A3-1-HART/AC615-20-1 with 50 ft. of cable

Unit Price \$14,975.00

Total Price: \$14,975.00

Prices listed do not include any applicable taxes, set-up, training or freight charges.

PLEASE ISSUE ORDER TO:

Patten Systems, Inc. 15598 Producer Lane Huntington Beach, CA 92649

Materials purchased will be shipped and invoiced directly by Patten Systems, Inc.

Shipment can be made in approximately 14-16 weeks from receipt of order. Terms of payment are Net 30 days from invoice date, F.O.B. El Monte, CA. Prices quoted are firm for 30 days from this date.